KADUR DIVISION.

ADVERTISEMENT.

The 28th November 1891.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 21st December 1891, for increasing the capacity of the Madag Tank, Kadur Taluk, Registered No. I. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1892.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for increasing the capacity of Madag Tank, Kadur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract.

Items of Work.	Per.	Rate.	Quantity.
Bund.			
Earthwork including forming, watering and tamping ..	C. Yd.		6,082
Rough stone work, new	Do		797
Turfing the front slope	S. Yd.		357
Cutting and re-filling a trench for examining the leak in the tank bund	Lump sum		
Sluice.			
Repairing the sluice if found necessary	Do		
Waste Weir 100 *feet long.*			
Removing the rough stone revetment	Do		
Earthwork, excavating foundation, deep cutting.. .	C. Yd.		955
Stepping in rock for foundation	Do		38
Rough stone in surki mortar including pointing.. ..	C. Ft.		21,944
Burnt brick in surki mortar	Do		5,837
Plastering with surki mortar	Sqr.		27·65
Burnt stone slabs	S. Ft.		7 59

A. GOVINDACHARLU,
Executive Engineer.

REDUCTION IN PRICE OF CINCHONA FEBRIFUGE.

From 1st April 1891, and until further orders, Cinchona Febrifuge can be purchased by all Government officers and by any one taking *ten pounds* at a time, from the Superintendent, Botanic Garden, Calcutta, at the following rates: four ounce tin *Rs.* 2, *ans.* 8; eight ounce tin *Rs.* 5; one pound tin *Rs.* 10.—The general public can be supplied by the Superintendent, Botanic Garden, *for Cash only* at the undernoted rates: per four ounce tin *Rs.* 3; per eight ounce tin *Rs.* 6; per pound tin *Rs.* 12. This medicine is also sold by the principal European and Native druggists in Calcutta. Postage four annas per 4 *oz.* tin, eight annas per 8 *oz.* tin, and twelve annas per pound tin, in addition to the foregoing rates.